

The Global Energy Challenge: Reviewing the Strategies for Natural Gas

# REDUCING FUGITIVE EMISSIONS FROM GAS DISTRIBUTION SYSTEMS BY THE SYSTEMATIC APPLICATION OF PRESSURE PROFILING TECHNOLOGY

Steven Vallender
Asset Strategy Manager – Gas Distribution UK
National Grid plc

Committee Session 4.2: Wednesday 7 October







The Global Energy Challenge: Reviewing the Strategies for Natural Gas

### Agenda

- 1. Environmental emissions
- 2. Leakage mitigation technologies
- 3. Pressure management
- 4. How profile control works
- 5. Profile control technology
- 6. National Grid's profiler installation programme









The Global Energy Challenge: Reviewing the Strategies for Natural Gas

#### 2. Leakage mitigation technologies

There are several technologies available...







- Replacing pipes reduces leakage by a factor of 50 – so it's a very effective technique.
- It is possible to treat joints using by Reducing pressure reduces leakage. chemicals carried by the gas.

- However, it is very expensive and as a result the rate of return is typically <1%
- Chemicals toxic and only address joint leakage. Different chemicals for different joints complicating implementation.
- This technology is widely applicable, easy to deploy and cost effective but does not improve the pipe itself.







The Global Energy Challenge: Reviewing the Strategies for Natural Gas


# Pressure management


- Customers require an adequate pressure to safely operate their appliances.
- However the higher the pressure within the mains the more leakage.
- Pressure management reduces operating pressures at times of low demand.
- There is a trade off between precision of control action and cost, particularly telemetry cost.













The Global Energy Challenge: Reviewing the Strategies for Natural Gas

## 6. National Grid's profiler installation programme

- As of April 2008 National Grid had 3,500 profile control systems
  - At 1 Aug 09 over 1,000 new units had been installed
  - target is 5,500 by April 2010
- Investment c. £23m over two years to deliver nearly 2,000 units.
- c. 5% reduction in leakage, over 125,000 tonnes CO2 equivalent on an ongoing basis.





